



ESTIMATE

Tidewater Home Improvement LLC

Class B Contractor #2705172863

414 Worster Ave

Hampton, Virginia 23669

United States

(757) 551-6413

tidehomepro.com

BILL TO

John Finney

John Finney

1013 Dulcie Ave

Virginia Beach, VA 23455

United States

mafinney@yahoo.com

Estimate Number: 1343

Estimate Date: September 3, 2026

Valid Until: September 10, 2026

Grand Total (USD): \$6,054.00

Clean Up & Debris Removal

Clean up the 2,506 sq ft crawlspace - remove all trash, debris, and the improperly installed vapor barrier and haul away from the home.

10mil Vapor Barrier

Measure on-site and install a new 10-mil vapor barrier over the crawlspace floor (2,506 sq ft), secured with crawlspace staples or wire pins.

Dehumidifier Condensate pump

Replace the damaged condensate pump - new pump supplied and installed.

Dehumidifier Filter Replacement

Replace the dehumidifier filter (E80). Existing dehumidifier is working and stays.

Seal Vents

Seal all crawlspace vents from the inside (currently not sealed properly).

Grand Total (USD):

\$6,054.00

Notes / Terms

SCOPE OF WORK:

- Clean Up & Debris Removal: Remove ground debris, trash, and the improperly installed old vapor barrier from the crawlspace and away from the home. 2,506 sq ft.
- Vapor Barrier 10 mil: Measure on-site and install a new 10-mil vapor barrier with pier overlap, secured with crawlspace staples or wire pins. 2,506 sq ft.
- Condensate Pump: Replace the damaged condensate pump with a new condensate pump, supplied and installed.
- Dehumidifier Filter Replacement: Replace the dehumidifier filter (E80 model). The existing dehumidifier is working and stays.
- Seal Vents: Seal all crawlspace vents from the inside to eliminate outside air from entering.

NOT INCLUDED:

for Estimate #1343

Page 1 of 2



-
- Replacement dehumidifier (existing unit is working and stays)
 - Insulation
 - Permits

Notes:

**Jobsite will be left clean once completed.

Warranty:

**12 months workmanship on the project.

Payment Terms:

Total Project Cost: \$6,054.00

Deposit to Schedule: \$3,027.00

Final Payment: \$3,027.00

Check is a preferred method.

**You can pay by credit card using the link below.

<https://request.plastiq.com/pay-tidewater-home-improvement-llc>

Cards not eligible for payment:

- Virtual Affirm credit card

Validity: valid until September 10, 2026.